MYSORE DIVISION.

Notification dated 18th February 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 18th March 1931, for constructing Sri Kannambadi Amma's Temple at Abbur, Periyapatna Sub-Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred only in cash or Government Promissory Notes as earnest money and be superscribed "Tender for constructing Sri Kannambadi Amma's Temple at Abbur, Periyapatna Sub-Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered, cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tendered rates will not be enhanced on any account.

10. The rates should be clearly written both in figures and words.

11. L. S. rates at per cent above or below sanctioned will not be accepted.

Abstract estimate for constructing Kannambadi Amma's Temple at Abbur, Sub-Taluk

Sl. No.	Items of work	Quantity	Per	Rates		Cost
				In words	In figures	
						Rs.
	Constructing Garbhagudi.—					
1	Earthwork excavating foundation and filling basement.	76	C.yd.			
2	Concrete in mortar	598	C.ft.			
3	Stone in mortar	1,072	,,			
4	Size stone in mortar dressing the exposed portion and joints.	495	,,			
5	Burnt brick in mortar	1,219	,,			
6	Burnt brick in mortar arch work ...	30	,,			
7	Burnt stone slabs 6" thick nicely dressed ...	1,021	S.ft.			
8	Cut stone pillars nicely dressed ...	63	C.ft.			
9	Do bases do	10	Each			
10	Do capitals or bothiges four sided nicely dressed.	10	,,			
11	Do beams including cutting grooves ...	161	C.ft.			
12	Plastering with chunam plain ...	8·28	Sqr.			
13	Do do ornamental work such as cornice flower work to Gopuram and walls out side.	5·93	,,			
14	Ceiling plastering with flower work ...	3·45	,,			
15	Putting 3" concrete and plastering ...	2·56	,,			
16	Lovy cornice complete as per-elevation ...	117	R.ft.			
17	Ornamental masonry parapet wall including top cornice, etc., complete.	72	,,			
18	Teakwood frame and wire mesh fan light, complete.	2	S.ft.			
19	Teakwood door with battened shutters 1½" thick with iron hinges, etc.	14	,,			
20	Mortar architraves 6" wide 1½" thick ...	47	R.ft.			

Sl. No.	Items of work	Quantity	Per	Rate In words	Rate In figures	Cost
						Rs.
	Constructing Mahadwara or front entrance,—					
1	Earthwork excavating foundation ...	340	C.yd.			
2	Concrete in mortar	2,052	C.ft.			
3	Stone in mortar foundation	4,725	„			
4	Cut stone in mortar basement	790	„			
5	Dressing the cornice mouldings, etc., in cut stone.	745	S.ft.			
6	Burnt brick in mortar superstructure and Gopuram.	6,009	C.ft.			
7	Cut stone pillars and beams nicely dressed ...	436	„			
8	Dressing the ornamental work in door frame (stone).	90	S.ft.			
9	Burnt stone slabs 6" thick	908	„			
10	Do 9" thick	594	„			
11	Plain chunam plastering	3·66	Sqr.			
12	Ornamental plastering such as cornice, lovy, small vimanams and flower work for Gopuram.	11·20	„			
13	Lovy heavy cornice work including slab and mortar.	108	R.ft.			
14	Teakwood window frame and wood railing only	20	S.ft.			
15	Copper final including fixing ...	Lump	sum			
16	Iron sliding door complete ...	98	S.ft.			
17	Scafolding charges and other sundry items ...	Lump	sum			
	Constructing compound wall,—					
1	Excavating foundation ...	52	C.yd.			
2	Burnt brick in surki mortar ...	4506	C.ft.			
3	Plastering with surki mortar ...	82·90	Sqr.			
4	Coping with burnt brick in mortar and plastering, etc., complete.	829	R.ft.			
	Flooring temple,—					
1	Flooring with ½ ft. depth cement concrete with cement plastering at top complete.	160	C.ft.			

K. NARAYANA IYENGAR,
Executive Engineer.